



TEST REPORT

DATE: 05-24-2024

Page 1 of 1

TEST NUMBER: 0307960

| | |
|---------------|----------|
| CLIENT | Go Green |
|---------------|----------|

| | |
|------------------------------|---|
| TEST METHOD CONDUCTED | ASTM F1551 Water Permeability of Synthetic Turf Systems and Permeable Bases, DIN 18-035 |
|------------------------------|---|

| DESCRIPTION OF TEST SAMPLE | |
|----------------------------|------------|
| IDENTIFICATION | Petmaxx 50 |
| ROLL NUMBER | G38463B |
| CONSTRUCTION | Turf |
| REFERENCE | PO #17807 |

GENERAL PRINCIPLE

The test procedure is used to determine the flow rate of rainfall through a material. A volume of water is poured through the surface and timed. Calculations are then made on the inches of water that would pass through the substrate per hour. The sample was tested as received.

TEST RESULTS

| SAMPLE IDENTIFICATION | RESULTS |
|-----------------------|-------------------------------|
| Aquamaxx 50 | 796.6 Inches/Hour |
| | 7.78 Sec/6" zone |
| | 259.6 Gal/min/yd ² |

APPROVED BY:

This report is provided for the exclusive use of the client to whom it is addressed. It may be used in its entirety to gain product acceptance from duly constituted authorities. This report applies only to those samples tested and is not necessarily indicative of apparently identical or similar products. This report, or the name of Professional Testing Laboratory, LLC, shall not be used under any circumstance in advertising to the general public.